

NOTICE TO BIDDERS

PL-566 Flood Control Dam Mowing

The Garrett Soil Conservation District is accepting bids for mowing three (3) PL-566 Flood Control Dams, including cutting of herbaceous and woody vegetation at end of outlet pipe and edge of plunge pool. The dams are located at Deer Park, Loch Lynn and Route 219 north of Oakland.

Pre-bid conference and site-showings will be held at the Garrett SCD office at 1916 Maryland Highway Ste C Mt. Lake Park MD on June 22 at 9:00 a.m.

Bid forms and specifications are available at the Garrett Soil Conservation District Office located at 1916 Maryland Highway, Suite C, Mt. Lake Park, MD or on the Districts website at GarrettSCD.org. Sealed bids will be accepted until 4:00 p.m., June 29, 2017. Bids will be opened June 29, 2017 at 4:15 p.m. at the Garrett SCD office. Bidders and interested parties are welcome to attend the bid opening.

Work may commence anytime after the Agreement is signed by both the Contractor and the District but no later than July 6, 2017 and must be completed by July 28, 2017. For more information call the District office at 301-334-6951. The District reserves the right to reject any and all bids.

Garrett Soil Conservation District

PL- 566 Mowing Specifications (2017)

Attachment "C" - Dam # 7



Scale: 1" = 200'



Aerial Photo - FSA2011
Map By: GSCD - RCK

Garrett Soil Conservation District

PL- 566 Mowing Specifications (2017)

Attachment "B" - Dam # 5



Scale: 1" = 200'



Aerial Photo - FSA 2011
Map By: GSCD - RCK

Garrett Soil Conservation District
PL- 566 Mowing Specifications (2017)

Attachment "A" - Dam # 2



Scale: 1" = 200'



Aerial Photo - FSA 2011
Map By: GSCD - RCK

CONTRACTOR AGREEMENT

THIS AGREEMENT made the _____ day of _____, 2017 by and between _____, hereinafter call the **Contractor** and **Garrett Soil Conservation District**, hereinafter called the **Sponsor**.

Article 1. Scope of Work:

The Contractor shall furnish all materials, equipment and labor to mow PL-566 flood control impoundments Nos. 2, 5 and 7 of the Little Youghiogheny Watershed Flood Control Project. The area to be mowed for each dam is shown on attachments A, B and C and consists of the entire embankment from the edge of the water to the toe on the downstream slope and the emergency spillway, including hand cutting or "weedeating" of herbaceous and woody vegetation at end of outlet pipe and edge of plunge pool. Woody vegetation one (1) inch and greater in diameter shall be cut no more than four (4) inches above ground level to a distance of five (5) feet up the side slopes from the bottom of the emergency spillway and disposed of at a site approved by Garrett Soil Conservation District.

ADDITIONAL WORK FOR Dam #7

Mow 4 feet on both sides of access road from the gate to the dam as shown on the attachment. Remove any logs, trees, brush or woody material from the dam plunge pool and exit (stream) channel to a distance of 75 feet downstream from end of the outlet pipe. Material shall be disposed of onsite at a distance from the edge of the stream acceptable to the Garrett SCD.

Article 2. Time of Completion:

The work to be performed under this contract shall be completed by July 28, 2017 and may commence any time after Agreement is signed by both Contractor and the District but no later than July 6, 2017.

Article 3. Contract Price:

The Sponsor shall pay the Contractor the sum of \$ _____ upon satisfactory completion of the work performed under this contract.

Article 4. General Provisions:

1. Vegetation to be cut to a finished height of 4 to 6 inches.
2. All work shall be completed in a workman-like manner and incompliance with all codes and applicable laws.
3. To the extent required by law, all work shall be performed by individuals duly licensed and authorized by law to perform said work.
4. Contractor warrants it is adequately insured for injury to its employees and others incurring loss or injury as a result to the acts of Contractor or its employees or subcontractors.
5. Contractor shall, at its own expense, obtain all permits necessary for the work performed.
6. The Garrett Soil Conservation District and/or landowners are not responsible for accidents. The Contractor, upon agreeing to perform the work, assumes all risk.

Garrett Soil Conservation District

(Name of Sponsor)

_____ (Name of Contractor)

By: _____
(Signature) (Date)

By: _____
(Signature) (Date)

1916 Maryland Highway Suite C
Mt. Lake Park MD 21550